3593 Medina Road #145
Medina, Ohio 44256
261-961-4399
License #16432
PROPOSAL ID: LA-2025-1001

Date: 01/29/2025

Proposal Submitted To:
Alex Ogilvie
3898 Faversham Rd
University Heights, OH 44118
alix.b.ogilvie@gmail.com
(415) 816-6174

Work To Be Performed At:
Alex Ogilvie
3898 Faversham Rd
University Heights, OH 44118

Review:

OPTION 1: Proposal to replace sanitary and storm clean-out tees and risers.

OPTION 2: Proposal to replace sanitary and storm sewer from front of house to clean-out tees.

THIS PRICE INCLUDES THE COST OF LABOR AND MATERIALS PROVIDED BY L&A PLUMBING - HEATING - COOLING LLC.

THIS PRICE IS AN ESTIMATE AND IS SUBJECT TO CHANGE DUE TO UNFORSEEN CIRCUMSTANCES AND OR CHANGES IN THE ORIGINAL JOB SCOPE.

LIMITED WARRANTY: ALL MATERIALS, PARTS, AND EQUIPMENT ARE WARRANTED BY THE MANUFACTURES WRITTEN WARRANTY ONLY: ALL LABOR PERFORMED BY L&A PLUMBING - HEATING - COOLING LLC IS WARRANTED FOR 1 YEAR FROM THE DATE OF INSTALLATION OR REPAIRS MADE.

Scope Of Work:

OPTION 1: Replace sanitary and storm clean-out tees and risers.

1. Contact OUPS to mark underground utilities before starting work.
2. Dig up with excavator to expose sanitary and storm clean-out tees.
3. Replace bot clean-out tees and risers in pvc pipe.
4. Replace problem section of pipe near clean-out tee.
5. Snake and camera both lines.
6. Backfill pipe in stone.
7. Backfill ditch to grade.

NOTE: Price includes cost of plumbing work and excavation work.

COST: $3,950.00

OPTION 2: Replace sanitary and storm sewer from front of house to clean-out tees.

1. Contact OUPS to mark underground utilities before starting work.
2. Dig with excavator from front of house to clean-out tees to expose sewer lines.
3. Replace sanitary and storm sewer in pvc pipe and fittings.
4. Make connections from downspout tie ins as needed.
5. Install new clean-out tees and risers for storm and sanitary sewer.
6. Backfill pipe in stone.
7. Backfill ditch to grade.

NOTE: Price includes cost of plumbing work and excavation work.

COST: $8,750.00

Cost:

Payment Terms: Upon Receipt

Legal:
TERMS AND CONDITIONS

1. All materials guaranteed to be as specified in scope of work. All work will be completed according to standard practice and in a good, workmanlike manner.
2. Unless specified stated othe wise above, repairr of streets, sidewalks and the like shall not be the responsibility of L&A. In the event excavation is required, the excavated area will be graded to ground level and mounded to allow for settlement. All landscaping required for completion of the job shall be the customer's responsibility.
3. In the event circumstances arise in the courre of performance which necessitate a deviation from the work described below or if the customer request that additional or different work be performed and the additional charge shall be agreed upon before the additional work is undertaken and a new written work description shall be executed.
4. Customer to provide all necessary easements and rights of way, unless otherwise noted.
5. No modifications of this agreement shall be valid unless in writing and signed by both parties.
6. Customer shall maintain fire, tornado, earthquake, and other necessary insurance on the property on which the work is performed. L&A shall maintain worker's compensation and public liability insurance.
7. This proposal constitutes our entire agreement and maybe withdrawn by us if not accepted within 30 days. No modifications of this agreement shall be valid unless in writing and signed by both parties.
8. Warranty is non-transferable, unless stated otherwise.

Note: This proposal may be withdrawn if not accepted within 30 days.

WE ARE LICENSED, BONDED AND INSURED FOR YOUR PROTECTION

Customer Signature: _____ Date: _____