



3593 Medina Road #145

Medina, Ohio 44256

261-961-4399

License #16432

**PROPOSAL ID: LA-2024-857**

**Date:** 09/29/2024

**Proposal Submitted To:**

Bob Masternak  
3960 Cook Rd  
Medina, OH 44256  
masternak@zoominternet.net  
(330) 289-6842

**Work To Be Performed At:**

Bob Masternak  
3960 Cook Rd  
Medina, OH 44256

**Review:**

Proposal to install new air handler in attic space and new a/c condenser.

NOTE: THERE ARE 3 OPTIONS ON THIS PROPOSAL.

THIS PRICE INCLUDES THE COST OF LABOR AND MATERIALS PROVIDED BY L&A PLUMBING - HEATING - COOLING LLC.

THIS PRICE IS AN ESTIMATE AND IS SUBJECT TO CHANGE DUE TO UNFORSEEN CIRCUMSTANCES AND OR CHANGES IN THE ORIGINAL JOB SCOPE.

LIMITED WARRANTY: ALL MATERIALS, PARTS, AND EQUIPMENT ARE WARRANTED BY THE MANUFACTURERS WRITTEN WARRANTY ONLY: ALL LABOR PERFORMED BY L&A PLUMBING - HEATING - COOLING LLC IS WARRANTED FOR 1 YEAR FROM THE DATE OF INSTALLATION OR REPAIRS MADE.

**Scope Of Work:**

**OPTION 1:**

1. Remove and discard existing air handler and a/c condenser.
2. Install new RUUD Endeavor 4 ton 2 stage air handler in attic space.
3. Install new RUUD Endeavor 3 ton 13.4 SEER2 1 stage cooling a/c condenser on new poly pad.
4. Install new drain pan for air handler.
5. Install new Honeywell media cabinet and filter.
6. Install new condensate pump and condensate drain piping.
7. Install EAZY-TRAP with safety switch.
8. Install WET-SWITCH safety switch in drain pan.
9. Install new ProStat T715 digital programmable thermostat - 2heat/2cool.
10. Electrical work as needed.
11. Sheet metal work as needed.
12. Add R-410A refrigerant as needed.
13. Complete system start-up.

COST: \$9,975.00

**OPTION 2:**

1. Remove and discard existing air handler and a/c condenser.
2. Install new RUUD Endeavor 4 ton 2 stage air handler in attic space.
3. Install new RUUD Endeavor 3 ton 15 SEER2 3 stage cooling a/c condenser on new poly pad.
4. Install new drain pan for air handler.
5. Install new Honeywell media cabinet and filter.
6. Install new condensate pump and condensate drain piping.
7. Install EAZY-TRAP with safety switch.
8. Install WET-SWITCH safety switch in drain pan.
9. Install new ProStat T715 digital programmable thermostat - 2heat/2cool.
10. Electrical work as needed.
11. Sheet metal work as needed.
12. Add R-410A refrigerant as needed.
13. Complete system start-up.

COST: \$10,650.00

**OPTION 3:**

1. Remove and discard existing air handler and a/c condenser.
2. Install new RUUD Endeavor 4 ton 2 stage air handler in attic space.
3. Install new RUUD Endeavor 3 ton 15 SEER2 Heat Pump 2 stage cooling a/c condenser on new poly heat pump pad.
4. Install new drain pan for air handler.
5. Install new Honeywell media cabinet and filter.
6. Install new condensate pump and condensate drain piping.
7. Install EAZY-TRAP with safety switch.
8. Install WET-SWITCH safety switch in drain pan.
9. Install new ProStat T955 digital programmable Heat Pump thermostat - 2heat/1cool.
10. Electrical work as needed.
11. Sheet metal work as needed.
12. Add R-410A refrigerant as needed.
13. Complete system start-up.

COST: \$12,150.00

**Cost:**

**Payment Terms:** Upon Receipt

**Legal:**

**TERMS AND CONDITIONS**

1. All materials guaranteed to be as specified in scope of work. All work will be completed according to standard practice and in a good, workmanlike manner.
2. Unless specified stated otherwise above, repair of streets, sidewalks and the like shall not be the responsibility of L&A. In the event excavation is required, the excavated area will be graded to ground level and mounded to allow for settlement. All landscaping required for completion of the job shall be the customer's responsibility.
3. In the event circumstances arise in the course of performance which necessitate a deviation from the work described below or if the customer request that additional or different work be performed and the additional charge shall be agreed upon before the additional work is undertaken and a new written work description shall be executed.
4. Customer to provide all necessary easements and rights of way, unless otherwise noted.
5. No modifications of this agreement shall be valid unless in writing and signed by both parties.
6. Customer shall maintain fire, tornado, earthquake, and other necessary insurance on the property on which the work is performed. L&A shall maintain worker's compensation and public liability insurance.

7. This proposal constitutes our entire agreement and maybe withdrawn by us if not accepted within 30 days. No modifications of this agreement shall be valid unless in writing and signed by both parties.
8. Warranty is non-transferable, unless stated otherwise.

Note: This proposal may be withdrawn if not accepted within 30 days.

**WE ARE LICENSED, BONDED AND INSURED FOR YOUR PROTECTION**

Customer Signature:

Date:

---